
MATCH LINE A
MATCH LINE B
MATCH LINE C
LONE PINE DRIVE
SHERMAN AVENUE
(50' WIDE PUBLIC ROAD)
NEW JERSEY TRANSIT CORPORATION CLASS I
(FORMERLY ERIE-LACKAWANNA RAILROAD)
PASSAIC & DELAWARE DIVISION
(100' WIDE R.O.W. PER "DLT MAP")
TAX LOT 3 BLOCK 703 (PER TAX MAP)
TAX LOT 4 BLOCK 703 (PER TAX MAP)
TAX LOT 5 BLOCK 703 (PER TAX MAP)
TAX LOT 6 BLOCK 703 (PER TAX MAP)
TAX LOT 17 BLOCK 703 (PER TAX MAP)
TAX LOT 18 BLOCK 703 (PER TAX MAP)
TAX LOT 2 BLOCK 703 (PER TAX MAP)
TAX LOT 1 BLOCK 704 (PER TAX MAP)
TAX LOT 2 BLOCK 704 (PER TAX MAP)
TAX LOT 3 BLOCK 704 (PER TAX MAP)
TAX LOT 4 BLOCK 704 (PER TAX MAP)
TAX LOT 5 BLOCK 703 (PER TAX MAP)
TAX LOT 6 BLOCK 703 (PER TAX MAP)
TAX LOT 7 BLOCK 703 (PER TAX MAP)
TAX LOT 8 BLOCK 703 (PER TAX MAP)
TAX LOT 14 BLOCK 703 (PER TAX MAP)
TAX LOT 15 BLOCK 703 (PER TAX MAP)
TAX LOT 16 BLOCK 703 (PER TAX MAP)
TAX LOT 19 BLOCK 703 (PER TAX MAP)
TAX LOT 20 BLOCK 703 (PER TAX MAP)
TAX LOT 21 BLOCK 703 (PER TAX MAP)
TAX LOT 22 BLOCK 703 (PER TAX MAP)
TAX LOT 23 BLOCK 703 (PER TAX MAP)
TAX LOT







VICINITY MAP
SCALE: N.T.S.

SYMBOL LEGEND

CONC. MONUMENT FND	MAIL BOX
I.P. / I.R. FND	CABLE TV BOX
TACK / STAKE FND	TELEPHONE BOX
WETLAND FLAG	A/C UNIT
SPOT ELEVATIONS	TRANSFORMER
TRAFFIC SIGNAL POLE	ELECTRIC METER
UTILITY POLE	GAS METER
GUY WIRE	WATER METER
UTILITY POLE W/LIGHT	WATER VALVE
LIGHT POLE	GAS VALVE
SIGN	CLEAN OUT
FIRE HYDRANT	SPRINKLER HEAD
BOLLARD	GAS
MONITORING WELL	WATER
WELL	ELECTRIC
MANHOLE	TELEPHONE
"A"-INLET	CABLE TV
"B"-INLET	TREE
"E"-INLET	SHRUB
YARD INLET	(S) SURVEY DIMENSION
FLARED END SECTION	(D) DEED DIMENSION
D.C. DEPRESSED CURB	TB TOP OF BANK
L.S.A. LANDSCAPED AREA	T.R. TOP OF RAILROAD TRACK

BASIS OF BEARING

NEW JERSEY STATE PLANE COORDINATE GRID NAD 83

TITLE INFORMATION

THE TITLE COMMITMENT WAS PREPARED BY FIRST SERGEN TITLE AGENCY AN AGENT FOR CHICAGO TITLE INSURANCE COMPANY, FILE NO. H16-0458 DATED NOVEMBER 3, 2016.

SURVEYOR CERTIFICATION

TO:

HCRT INVESTMENTS, LLC
FIRST SERGEN TITLE AGENCY, AS AGENT FOR
CHICAGO TITLE INSURANCE COMPANY

THIS IS TO CERTIFY THAT THIS MAP OR PLAT AND THE SURVEY ON WHICH IT IS BASED WERE MADE IN ACCORDANCE WITH THE 2011 MINIMUM STANDARD DETAIL REQUIREMENTS FOR ALTA/NSPS LAND TITLE SURVEYS, JOINTLY ESTABLISHED AND ADOPTED BY ALTA AND NSPS, AND INCLUDES ITEMS 2, 3, 4, 6a, 6b, 7a, 7b1, 7c, 8, 9, 11, 13, 14, 16, 17 AND 19 OF TABLE A THEREOF. THE FIELD WORK WAS COMPLETED ON NOVEMBER 14, 2016.

(SIGNED)_____(SEAL) DATE:_____

JAMES J. HEISER
NJ LIC. 24GS04531100
NY LIC. 050321

FLOOD INFORMATION

BY GRAPHIC PLOTTING ONLY, THE PREMISES IS LOCATED IN ZONE X (AREAS DETERMINED TO BE OUTSIDE THE 0.2% ANNUAL CHANCE FLOODPLAIN) PER COMMUNITY PANEL NUMBER 17 OF 45, MAP NUMBER 34039C0017F, EFFECTIVE DATE SEPTEMBER 30, 2008. NO FIELD SURVEYING WAS PERFORMED TO DETERMINE THIS ZONE. AN ELEVATION CERTIFICATE MAY BE NEEDED TO VERIFY THIS DETERMINATION OR APPLY FOR A VARIANCE FROM THE FEDERAL EMERGENCY MANAGEMENT AGENCY.

OBSERVED UTILITY SERVICES

SANITARY SEWER - TOWNSHIP OF BERKELEY HEIGHTS
ELECTRIC - PSE&G
GAS - PSE&G
WATER - NJ AMERICAN WATER

MAP REFERENCES

1. MAP ENTITLED "FINAL FLOOD INSURANCE RATE MAP, UNION COUNTY, NEW JERSEY (ALL JURISDICTIONS)," PANEL 17 OF 45, MAP NUMBER 34039C0017F, EFFECTIVE DATE SEPTEMBER 30, 2008.
2. MAP ENTITLED "SURVEY OF PROPERTY KNOWN AS TAX MAP LOT 6 BLOCK 705 SITUATED IN THE TOWNSHIP OF BERKELEY HEIGHTS, UNION COUNTY, N.J.," PREPARED BY THOMAS SIRI ESTING & PLANNING CO., INC., DATED 10-14-86.
3. MAP ENTITLED "SURVEY OF PROPERTY LOT 15, BLOCK 702, LOT 3, BLOCK 703 LONE PINE DRIVE, TOWNSHIP OF BERKELEY HEIGHTS, UNION COUNTY, NEW JERSEY" PREPARED BY DPK CONSULTING, LLC AND DATED MAY 14, 2002.

30 15 0 30 60 90

SCALE: 1"=30'

DESCRIPTION OF PROPERTY

SCHEDULE A - LEGAL DESCRIPTION

FIRST TRACT

COMMENCING AT THE END OF THE NINTH COURSE IN A DEED FROM JUNIUS H. STONE, ET UX, TO JUNIUS H. STONE CORPORATION, BY A DEED DATED NOVEMBER 1, 1920 AND RECORDED AT THE UNION COUNTY CLERK'S OFFICE IN DEED BOOK 836 PAGE 522 THENCE

(A) SOUTH 1 DEGREES 08 MINUTES 00 SECONDS EAST, A DISTANCE OF 36.23 FEET TO THE POINT OF BEGINNING; THENCE
(1) ALONG THE CENTER LINE OF A RIGHT-OF-WAY TWENTY FEET IN WIDTH, SOUTH 41 DEGREES 49 MINUTES 40 SECONDS EAST, A DISTANCE OF 439.17 FEET; THENCE
(2) SOUTH 19 DEGREES 51 MINUTES 00 SECONDS EAST, A DISTANCE OF 64.81 FEET; THENCE
(3) SOUTH 12 DEGREES 14 MINUTES 00 SECONDS WEST, A DISTANCE OF 206.15 FEET TO THE NORTHERLY RIGHT-OF-WAY LINE OF LAND NOW OR FORMERLY DELAWARE LACKAWANNA & WESTERN RAILROAD; THENCE
(4) ALONG THE NORTHERLY RIGHT-OF-WAY OF LAND NOW OR FORMERLY DELAWARE LACKAWANNA & WESTERN RAILROAD, NORTH 77 DEGREES 46 MINUTES 00 SECONDS WEST, A DISTANCE OF 536.37 FEET; THE FOLLOWING EIGHT COURSES RUNNING ALONG THE CENTER OF A BROOK; THENCE
(5) NORTH 06 DEGREES 49 MINUTES 16 SECONDS EAST, A DISTANCE OF 15.88 FEET; THENCE
(6) NORTH 15 DEGREES 30 MINUTES 51 SECONDS WEST, A DISTANCE OF 67.66 FEET; THENCE
(7) NORTH 19 DEGREES 27 MINUTES 35 SECONDS EAST, A DISTANCE OF 34.01 FEET; THENCE
(8) NORTH 45 DEGREES 27 MINUTES 00 SECONDS EAST, A DISTANCE OF 39.84 FEET; THENCE
(9) NORTH 36 DEGREES 24 MINUTES 15 SECONDS EAST, A DISTANCE OF 77.86 FEET; THENCE
(10) NORTH 22 DEGREES 31 MINUTES 37 SECONDS EAST, A DISTANCE OF 127.00 FEET; THENCE
(11) NORTH 26 DEGREES 11 MINUTES 05 SECONDS EAST, A DISTANCE OF 64.11 FEET; THENCE
(12) NORTH 31 DEGREES 05 MINUTES 34 SECONDS EAST, A DISTANCE OF 64.26 FEET; THENCE
(13) NORTH 39 DEGREES 53 MINUTES 42 SECONDS EAST, A DISTANCE OF 5.28 FEET TO THE END OF THE NINTH COURSE IN A DEED FROM JUNIUS H. STONE, ET UX, TO JUNIUS H. STONE CORPORATION, AFORESAID IN DEED BOOK 836 PAGE 522; THENCE
(14) ALONG THE FOURTH COURSE, IN A REVERSE DIRECTION, AS DESCRIBED IN A DEED FROM HILL VALLEY HOLDING CO. TO THE TOWNSHIP OF BERKELEY HEIGHTS, RECORDED IN DEED BOOK 2644 PAGE 05, SOUTH 29 DEGREES 04 MINUTES 30 SECONDS EAST, A DISTANCE OF 25.00 FEET TO THE POINT OF BEGINNING.
(15) SOUTHERLY AND SOUTHEASTERLY ALONG A CURVE CONCAVE TO THE SOUTH CONVEX TO THE NORTH HAVING A RADIUS OF 25.00 FEET, AN ARC DISTANCE OF 31.09 FEET, SAID CURVE HAVING A CHORD OF SOUTH 77 DEGREES 24 MINUTES 37 SECONDS EAST, A DISTANCE OF 29.13 FEET; THENCE
(16) ALONG THE SECOND COURSE, IN A REVERSE DIRECTION, AS DESCRIBED IN A DEED FROM HILL VALLEY HOLDING CO. TO THE TOWNSHIP OF BERKELEY HEIGHTS, RECORDED IN DEED BOOK 2644 PAGE 05, SOUTH 64 DEGREES 13 MINUTES 00 SECONDS EAST, A DISTANCE OF 25.00 FEET TO THE POINT OF BEGINNING.

SECOND TRACT

COMMENCING AT THE END OF THE NINTH COURSE IN A DEED FROM JUNIUS H. STONE, ET UX, TO JUNIUS H. STONE CORPORATION, BY A DEED DATED NOVEMBER 1, 1920 AND RECORDED AT THE UNION COUNTY CLERK'S OFFICE IN DEED BOOK 836 PAGE 522; THENCE

(A) ALONG THE CENTER LINE OF A RIGHT-OF-WAY TWENTY FEET IN WIDTH, KNOWN AS LONE PINE DRIVE, SOUTH 41 DEGREES 49 MINUTES 00 S EAST A DISTANCE OF 466.80 FEET; THENCE
(B) SOUTH 75 DEGREES 51 MINUTES 00 SECONDS EAST, A DISTANCE OF 64.81 FEET TO THE POINT OF BEGINNING; THENCE
(1) ALONG LAND FORMERLY RICHARD P. GRACE, SOUTH 78 DEGREES 51 MINUTES 00 SECONDS EAST, A DISTANCE OF 282.84 FEET; THENCE
(2) NORTH 12 DEGREES 14 MINUTES 00 SECONDS EAST, A DISTANCE OF 206.15 FEET; THENCE
(3) ALONG LAND FORMERLY RICHARD P. GRACE, SOUTH 74 DEGREES 33 MINUTES 00 SECONDS EAST, A DISTANCE OF 83.48 FEET; THENCE
(4) CONTINUING ALONG LAND FORMERLY RICHARD P. GRACE, SOUTH 11 DEGREES 27 MINUTES 00 SECONDS WEST, A DISTANCE OF 41.45 FEET TO THE NORTHERLY RIGHT-OF-WAY LINE OF LAND NOW OR FORMERLY DELAWARE LACKAWANNA & WESTERN RAILROAD; THENCE
(5) ALONG NORTHERLY RIGHT-OF-WAY LINE OF LAND NOW OR FORMERLY DELAWARE LACKAWANNA & WESTERN RAILROAD, NORTH 77 DEGREES 46 MINUTES 00 SECONDS WEST, A DISTANCE OF 360.00 FEET; THENCE NORTH 12 DEGREES 14 MINUTES 00 SECONDS EAST, A DISTANCE OF 208.15 FEET TO THE POINT OF BEGINNING.

SURVEYOR'S DESCRIPTION

METES AND BOUNDS DESCRIPTION

LOTS 3, 4 & 8 BLOCK 703
TOWNSHIP OF BERKELEY HEIGHTS
UNION COUNTY, NEW JERSEY

ALL THAT CERTAIN LOT, PIECE OR PARCEL OF LAND, SITUATED, LYING AND BEING IN THE TOWNSHIP OF BERKELEY HEIGHTS IN THE COUNTY OF UNION AND STATE OF NEW JERSEY.

COMMENCING AT THE END OF THE NINTH COURSE IN A DEED FROM JUNIUS H. STONE, ET UX, TO JUNIUS H. STONE CORPORATION, BY A DEED DATED NOVEMBER 1, 1920 AND RECORDED AT THE UNION COUNTY CLERK'S OFFICE IN DEED BOOK 836 PAGE 522; THENCE

(A) SOUTH 40 DEGREES 08 MINUTES 04 SECONDS EAST, A DISTANCE OF 36.23 FEET TO THE POINT OF BEGINNING; THENCE

COURSE 1. ALONG THE DIVIDING LINE BETWEEN TAX LOT 3 AND TAX LOT 6 IN BLOCK 703, SOUTH 40 DEGREES 08 MINUTES 04 SECONDS EAST, A DISTANCE OF 439.17 FEET; THENCE

COURSE 2. SOUTH 85 DEGREES 11 MINUTES 04 SECONDS EAST, A DISTANCE OF 317.79 FEET; THENCE

COURSE 3. CONTINUING ALONG LAND FORMERLY RICHARD P. GRACE, SOUTH 04 DEGREES 48 MINUTES 56 SECONDS WEST, A DISTANCE OF 190.84 FEET; THENCE

COURSE 4. ALONG LAND FORMERLY RICHARD P. GRACE, SOUTH 84 DEGREES 53 MINUTES 04 SECONDS EAST, A DISTANCE OF 83.48 FEET; THENCE

COURSE 5. CONTINUING ALONG LAND FORMERLY RICHARD P. GRACE, SOUTH 05 DEGREES 06 MINUTES 56 SECONDS WEST, A DISTANCE OF 41.45 FEET TO THE NORTHERLY RIGHT-OF-WAY LINE OF LAND NOW OR FORMERLY DELAWARE LACKAWANNA & WESTERN RAILROAD; THENCE

COURSE 6. ALONG THE NORTHERLY RIGHT-OF-WAY OF LAND NOW OR FORMERLY DELAWARE LACKAWANNA & WESTERN RAILROAD, NORTH 84 DEGREES 06 MINUTES 44 SECONDS WEST, A DISTANCE OF 896.37 FEET, THE FOLLOWING EIGHT COURSES RUNNING ALONG THE CENTER OF A BROOK; THENCE

COURSE 7. NORTH 63 DEGREES 51 MINUTES 03 SECONDS WEST, A DISTANCE OF 147.34 FEET; THENCE

COURSE 8. NORTH 45 DEGREES 30 MINUTES 35 SECONDS WEST, A DISTANCE OF 13.21 FEET; THENCE

COURSE 9. NORTH 29 DEGREES 38 MINUTES 25 SECONDS EAST, A DISTANCE OF 170.12 FEET; THENCE

COURSE 10. NORTH 17 DEGREES 25 MINUTES 44 SECONDS EAST, A DISTANCE OF 9.43 FEET; THENCE

COURSE 11. NORTH 39 DEGREES 57 MINUTES 46 SECONDS EAST, A DISTANCE OF 22.73 FEET; THENCE

COURSE 12. NORTH 30 DEGREES 40 MINUTES 00 SECONDS EAST, A DISTANCE OF 77.86 FEET; THENCE

COURSE 13. NORTH 21 DEGREES 11 MINUTES 55 SECONDS EAST, A DISTANCE OF 127.00 FEET; THENCE

COURSE 14. NORTH 25 DEGREES 52 MINUTES 08 SECONDS EAST, A DISTANCE OF 64.84 FEET; THENCE

COURSE 15. NORTH 31 DEGREES 46 MINUTES 56 SECONDS EAST, A DISTANCE OF 13.20 FEET; THENCE

COURSE 16. SOUTHEASTERLY AND NORTHEASTERLY ALONG A CURVE CONCAVE TO THE SOUTH (CURVING TO THE RIGHT) WITH A RADIUS OF 25.00 FEET, AN ARC DISTANCE OF 39.27 FEET, SAID CURVE HAVING A CHORD BEARING OF NORTH 46 DEGREES 24 MINUTES 00 SECONDS EAST, A DISTANCE OF 13.81 FEET; THENCE

COURSE 17. EASTERLY AND SOUTHEASTERLY ALONG A CURVE CONCAVE TO THE SOUTH (CURVING TO THE RIGHT) WITH A RADIUS OF 25.00 FEET, AN ARC DISTANCE OF 31.09 FEET; SAID CURVE HAVING A CHORD BEARING OF SOUTH 83 DEGREES 54 MINUTES 36 SECONDS EAST, A DISTANCE OF 29.13 FEET; THENCE

COURSE 18. ALONG THE SECOND COURSE, IN A REVERSE DIRECTION, AS DESCRIBED IN A DEED FROM HILL VALLEY HOLDING CO., TO THE TOWNSHIP OF BERKELEY HEIGHTS, RECORDED IN DEED BOOK 2644 PAGE 05, NORTH 41 DEGREES 51 MINUTES 56 SECONDS EAST, A DISTANCE OF 25.00 FEET TO THE POINT OF BEGINNING.

CONTAINING 215,366 SQUARE FEET, MORE OR LESS OR 5.0539 ACRES, MORE OR LESS OF LAND.

BEING THE SAME PREMISES AS DESCRIBED IN DEED BOOK 4766, AT PAGE 267 AND DEED BOOK 4766, AT PAGE 271 AND DEED BOOK 2855, AT PAGE 418 RECORDED IN THE UNION COUNTY CLERK'S OFFICE.

SURVEYOR'S NOTES

1. THIS SURVEY IS PREPARED IN ACCORDANCE WITH DOCUMENTS CONTAINED IN A COMMITMENT FOR TITLE INSURANCE PREPARED BY FIRST SERGEN TITLE AGENCY AS AGENT FOR CHICAGO TITLE INSURANCE COMPANY, FILE NO. H16-0458 DATED NOVEMBER 3, 2016.
2. THIS SURVEY REPRESENTS FIELD CONDITIONS AS OF NOVEMBER 14, 2016.
3. THE UTILITIES SHOWN HAVE BEEN LOCATED FROM EVIDENCE OBSERVED ON THE SURFACE ONLY OR HAVE BEEN SHOWN GRAPHICALLY PER SUPPLIED MATERIALS. PANTHER ENGINEERING & SCIENCE, INC. MAKES NO GUARANTEES THAT THESE UTILITIES SHOWN COMPRISE ALL SUCH UTILITIES IN THE AREA, EITHER IN SERVICE OR ABANDONED. PANTHER ENGINEERING & SCIENCE, INC. FURTHER DOES NOT WARRANT THAT THE UNDERGROUND UTILITIES SHOWN ARE IN THE EXACT LOCATION INDICATED. PANTHER ENGINEERING & SCIENCE, INC. HAS NOT PHYSICALLY LOCATED THE UNDERGROUND UTILITIES.
4. PREMISES ARE COMMONLY KNOWN AS LONE PINE DRIVE, BERKELEY HEIGHTS, NEW JERSEY.
5. ALSO KNOWN AS TAX LOTS 3, 4 & 8 IN BLOCK 703 AS SHOWN ON THE OFFICIAL TAX MAPS OF THE TOWNSHIP OF BERKELEY HEIGHTS, UNION COUNTY, NEW JERSEY.
6. A WESTERN WATCH AND DIRECTION HOT TO SET CORNER MARKERS HAS BEEN EMPLOYED FOR THE ULTIMATE CLOSURE PURSUANT TO P.L. 2003, C.141 (N.J.S.A. 46:26-3) AND N.J.A.C. 13:40-5.1(D).
7. THE HORIZONTAL AND VERTICAL DATUM IS BASED UPON TWO (2) HIVELY LEICA GX1230 GPS RECEIVERS AND KEYNET.
8. IF THIS DOCUMENT DOES NOT CONTAIN A RAISED SEAL OF THE UNDERSIGNED PROFESSIONAL, IT IS NOT AN AUTHORIZED ORIGINAL DOCUMENT.
9. ZONING INFORMATION TO BE PROVIDED BY INSURED.
10. THE SURVEYOR OBSERVED NO REGULAR PARKING SPACES AND NO HANDICAPPED PARKING SPACES AT THE TIME OF THE FIELD VISIT.
11. NO EVIDENCE OF CURRENT EARTH MOVING WORK WAS OBSERVED AT TIME OF FIELD WORK.
12. THE PROPERTY IS UNAWARE OF ANY PROPOSED CHANGES IN STREET RIGHT OF WAY LINES.
13. NO EVIDENCE WAS OBSERVED OF SITE USE FOR LANDFILL PURPOSES.
14. BASED ON THE SURVEYORS REVIEW OF THE NEW JERSEY DEPARTMENT OF ENVIRONMENTAL PROTECTION'S GIS "IMAP" THERE ARE NO INVESTIGATED WETLANDS ON SITE. THE SURVEYOR MAKES NO DETERMINATION OR DEFINITIVE STATEMENT AS TO THE PRESENCE OR ABSENCE OF WETLANDS ON THE SITE.
15. VEHICULAR ACCESS TO THE SUBJECT PROPERTY IS BY WAY OF CURB OPENINGS ALONG THE PUBLIC RIGHT OF WAYS KNOWN AS LONE PINE DRIVE WHICH PROVIDES ACCESS TO SPRINGFIELD AVENUE.

SCHEDULE 'B' SECTION II EXCEPTIONS

SCHEDULE B - SECTION II EXCEPTIONS
CHICAGO TITLE INSURANCE COMPANY
FILE NO. H16-0458

(10) RIGHT OF WAY AS SET FORTH IN DEED BOOK 716 PAGE 458 AND DEED BOOK 1025 PAGE 256. 15' WIDE PRIVATE RIGHT OF WAY ONLY 422 ALONG THE NORTHERLY LINE OF PREMISES AS DESCRIBED IN D.B. 716, PG. 458 AND DOES NOT EXTEND BEGINNING AND TERMINUS - APPROXIMATE CENTER LINE DESCRIPTION: BEGINNING AT A POINT IN THE S.E. 15'ch. R.O.W. 458, RUNNING WIDE ASSERTED TO WEST IN TOWN BANK OF BANGOR, ITS SUCCESSORS AND ASSIGNS TO PRIVATE RIGHT OF WAY IN, TO AND OVER AND EXISTING LOT 3, BLOCK 703, LYING ON PREMISES.
(11) RAILROAD SIDING AS SET FORTH IN DEED BOOK 716 PAGE 456 AND DEED BOOK 1025 PAGE 256 - NO RAILROAD SIDING FOUND AT THE TIME OF THE FIELD VISIT - NO DESCRIPTION PROVIDED FOR THIS EXACT LOCATION BUT IS DEPICTED AS A SIDING FROM THE MAIN LINE OF THE RAILROAD TO PREMISES - NOT PLOTTABLE.
(12) ELECTRIC POLE LINE USE AS SET FORTH IN DEED BOOK 1025 PAGE 256 - EXACT LOCATION NOT SPECIFIED - EXISTING UTILITY POLES AND APPURTENANCES SHOWN HEREON.
(13) ACCESS RIGHTS AS SET FORTH IN DEED BOOK 1025 PAGE 256 - SHOWN HEREON.
(14) UTILITY GRANT AS SET FORTH IN DEED BOOK 2521 PAGE 369 - EXACT LOCATION NOT PLOTTABLE - EXISTING POLES AND APPURTENANCES SHOWN HEREON.
(15) SANITARY SEWER EASEMENTS AS SET FORTH IN DEED BOOK 2345 PAGE 81, DEED BOOK 2345 PAGE 89 AND DEED BOOK 2482 PAGE 113 - SHOWN HEREON.
(16) DRAINAGE EASEMENTS AND CONSTRUCTION EASEMENT AS SET FORTH IN DEED BOOK 2644 PAGE 5 - SHOWN HEREON.
(17) DRAINAGE EASEMENT CROSSING PREMISES AS SHOWN ON THE MUNICIPAL TAX MAP OF THE TOWNSHIP OF BERKELEY HEIGHTS - SHOWN HEREON.
(18) TWENTY FOOT WIDE RIGHT OF WAY AS SHOWN ON THE MUNICIPAL TAX MAP OF THE TOWNSHIP OF BERKELEY HEIGHTS - SHOWN HEREON.

PARCEL AREAS

IDENTIFICATION

ITEM	SQUARE FEET	ACRES
APPARENT OVERLAP OF LOT 3, BLOCK 703	853	0.0195
APPARENT OVERLAP OF LOTS 1, BLOCK 703	6,015	0.1381
AREA - 12' WIDE PRIVATE RIGHT-OF-WAY	5,149	0.1182
SEMI-ARC BETWEEN LOT 3 & LOT 703, BLOCK 703	5,063	0.1163
OVERALL AREA TAX LOT 6, BLOCK 703	9,091	0.2087
OVERALL AREA TAX LOT 3, BLOCK 703	173,948	4.0293
OVERALL AREA TAX LOT 4, BLOCK 703	80,331	1.3980
OVERALL AREA TAX LOTS 3 & 4, BLOCK 703	234,277	5.4242
OVERALL AREA TAX LOTS 3, 4 & 8, BLOCK 703	245,368	5.6329
AREA OF TAX LOTS 3, 4 & 8, LESS APPARENT OVERLAP OF TAX LOTS 1 & 2	238,700	5.4798

NO.	DATE	DESCRIPTION	BY	CHKD	REV'D
4	10/19/2021	ADDITIONAL TIMES, WETLANDS AND UTILITY LOCATIONS	JJH	JAS	
3	09/13/2021	ADDED TAX LOT 8	TJD	JAS	
2	04/12/2021	REVISED PER CLIENT COMMENTS	RJT	JAS	
1	01/26/2021	REVISED BOUNDARY FOR LOT 3	RJT	JAS	

PARTNER
Engineering and Science, Inc.
(a DBA of Partner Assessment Corp. and Engineering Sans)

JAMES J. HEISER, P.L.S.
NJ PROFESSIONAL LAND SURVEYOR LIC. NO. 24GS04531100

411 Industrial Way West
Eatontown, NJ 07724
NJ Certificate of Authorization No. 24GA28229900

Tel.: 732.380.1700
Fax: 732.380.1701
http://www.partnereic.com

DATE: 10/19/2021

Date	Scale (H)	Drawn	Designed	Checked	Released
10/19/2021	1"=30' (V) 1"=n/a Scale	T.J.D.		C.C.B.	

Job No.	Drawing Number	Drawing Name	Sheet
162228900		16-1703ALTA.dwg	2 of 2

ALTA/NSPS LAND TITLE SURVEY
TAX LOTS 3, 4 & 8 BLOCK 703
LONE PINE DRIVE

SITUATED IN
TOWNSHIP OF BERKELEY HEIGHTS, UNION COUNTY, NEW JERSEY